


AMD Witwatersrand Basins Due Diligence

Presentation to Portfolio Committee 7 September 2011






TCTA Directive

- Ministerial directive 6 April 2011
- Emergency works in Witwatersrand Gold Fields comprising:
 - > Installation of pumps
 - > Construction of water treatment plants
 - Release treated water into river system
- Obtain environmental and regulatory approvals
- Funding via National Treasury (R225 million)
- Advise and assist DWA with O&M model
- Minister may direct to do more



Locality






Overview of current situation

Rainfall recharge, surface water losses, infrastructure breakdown, groundwater inflow

	Control of the contro	
NAVantara	Central	Eastern
Western	L CELLIAL	
	n	Dadia
I Basin	basii	Basın





Design Philosophy

- Design lifespan 30 to 50 years concrete structures
- High quality submersible pumps and pipework
 low maintenance 30 year lifespan
- Short-term solution to serve as first phase of long-term solution
- Plant capacity ECL maintained even during high inflows
- Site selection taking long-term solution into account





Technical Solution: Western Basin












Implementation of Immediate Solution

- Upgrade Rand Uranium treatment plant cater for up to 36MI/d
- Implementation agreement with RU
- Target date November 2011
- Discharge treated water to Tweelopiespruit
- Co-disposal of sludge to Wes Wits Pit
- Operating rule: solo until Aug 2012 then parallel with Short Term solution until ECL





Technical Solution: Western Basin

Implementation of short term solution

- New HDS plant to be erected on Randfontein Estate East – capacity 25 to 30 ml/pd
- Installation of new pumps and pipework in Rand Uranium Shaft 8
- Treated water transferred by pipeline to Tweelopiespruit
- Sludge disposal at West Wits Pit duel pipeline
- Commissioning date August 2012
- ECL level 165 m June 2013






Dewatering of the Western Basin


ECL = 165 m below Shaft 8

Predicted Drawdown in the Western Basin for Immediate and Short Term Solutions











Central Basin - ECL Level

■ ECL = 186m below SWV

Predicted Rate of Rise in the Central Basin for Average, Dry and Wet Periods








Technical Solution: Central Basin

- New HDS plant next to South West Vertical
 Shaft capacity 84 ml/pd
- CRG Ritz pumps
- Treated water transferred pipeline to EslburgSpruit
- Sludge co-disposal with Durban DRD Gold via duel lines
- Grey water DRD 20ml/pd
- Commissioning date August 2012
- ECL level 186 m/400



Dewatering of the Central Basin





























Eastern Basin ECL Level

ECL = 290m below Grootvlei Shaft 3

Predicted Rate of Rise in the Eastern Basin for Average, Dry and Wet Periods








Technical Solution Eastern Basin

- New HDS plant next to Grootvlei No 3 shaft capacity shaft 110ml/pd
- Installation of new pumps and pipework -Grootvlei No. 3 Shaft
- Treated water transferred pipeline to Blesbokspruit
- Sludge co-disposal at Daggafontein Tailings Storage Facility via duel lines
- Commissioning date June 2014
- ECL level 290m/ mines?



Generic Mine Water Neutralisation Process


















ACTIVITY	DATE
Receive directive	6 April 2011
Appoint PSP	9 May 2011
Complete due diligence	7 July 2011
Issue tenders	mid September 2011
Commission immediate solution (Western B)	November 2011
Contract award	November 2011
Start construction	January 2012
Project commissioning	Augustus 2012
Project closeout	December 2012



Capital Cost Budget

AMD (Phase 1) Capital Cost

Description	Grand-Total (R' million)
Construction	665
Western Basin: Immediate (Oct'11)	20
Western Basin: Short Term (Nov'12)	195
Central Basin: Short Term (Nov'12)	210
Eastern Basin: Short Term (May'13)	240
Engineering-Infrastructure	62
Environment	9
Total : Contr & Eng & Env	736

5%	Administration Cost		37
		Total: Administration Cost	37

Total: Excl Contingency & Escalation 772

15% Contingency		116	
		Total: After Contingency	888
6%	Escalation		36


Grand Total: Project Implementation Cost 924





AMD1 Operation & Maintenance Cost


Description	Monthly (R'million)	Annual (R'million)
Western Basin: Immediate (15 months)	5	55
Western Basin: Short Term (18 months)	8	101
Central Basin: Short Term (18 months)	11	128
Eastern Basin: Short Term (9 months)	8	101
Operations & Maintenance	32	385
















The Integrated Regulatory Process






Immediate Authorisation


Apply for Waste License to upgrade Rand Uranium Water Treatment Plant to handle the extra 18 MI/d that is decanting.



Complexity of Processes








Optimised Approach

Enabling Legislation

National Water Act (Act 36 of 1998)

Section 110 (2)(a) applies as the waterworks is deemed to be constructed in emergency circumstances





Communications Strategy

- Regulatory requirements for public participation (i.e. scoping requirements for environmental assessment in terms of the EIA regulations).
- Communication requirements for dissemination of project information.
- Engagement of stakeholders.





Rey Project Risks

Rek KHAOOIRE Project delay due to funding MTEF submission constraints - contract award **Budget reprioritization** subject to funding Accelerate long-term solution Optimize sale of "grey water" Severely limited timeframes Optimized procurement processes Accelerated approvals Environmental Establish authorities forum authorizations - delay Develop optimized approval project process – emergency project Poor state of existing Construct new infrastructure infrastructure impacting on Project lifespan 30 to 50 years project costs Reputational risk – high Communication strategy public interest Public participation Environmental degradation Accelerate long-term solution

